

# GREGG DRILLING PROJECT PORTFOLIO



## Scope of Work

Gregg Drilling completed an injection project in September of 2022 for Arcadis in Seal Beach, CA. The project required injection of 55,600 gallons of an Emulsified Vegetable Oil (EVO) solution into 17 direct push points targeting a treatment zone from 12-22ft.

## Highlights

- Top-down injection approach
- Up to 8 simultaneous injection locations
- Small injection footprint

## Challenges & Benefits

- Storage of (17) totes, nearly 4,200 gallons of EVO, at the Gregg yard reduced shipping and storage costs.
- Proper traffic control kept local businesses open, pedestrians safe, and did not impede on site production.
- Anoxic water was prepared in a 250 gallon tote onboard the injection system, reducing the overall site footprint.
- Gregg mobilized a limited access direct push rig for locations inside a commercial building

## Seal Beach ESIB Injection 2022

### Equipment/personnel:

- Custom injection platform
- Geoprobe 7822 & 420M



### Client Reference:

Dalia Rumani, Arcadis  
Dalia.Rumani@arcadis.com



[www.greggdrilling.com](http://www.greggdrilling.com)

